



October 16, 2006

Lennar Charleston
1941 Savage Road, Suite 100-C
Charleston, SC 29407
Attn: Mr. Michael Bottoms

Re: Indoor Air Quality/Methane Screening Report – Part I
Westcott Plantation – Pebble Creek Village
Summerville, SC
PSI Report No.: 465-60033-2

Mr. Bottoms:

As requested by Mr. Andrew Rothenberger, our representative was on site October 4 thru 16, 2006 at the above referenced property to perform a house to house survey of the interior and exterior spaces of the single family residences to assess the indoor air for the presence of methane. An itemized listing of the specific homes where testing was performed to date is attached, labeled *Summary of Indoor Air Testing by FID* (8 of 8 pages). For the purpose of this investigation, we are considering 5 ppm methane the threshold concentration above which additional investigation is warranted to locate the source of methane entering the home, and mitigate where possible.

The survey utilized a MicroFID Organic Vapor Analyzer (Serial No.: CZKE305) manufactured by Photovac, Inc. The detector was calibrated using a control gas (100 ppm methane) at the start and end of each day. Also, a fresh air calibration was conducted outside each residence immediately prior to performance of the survey. The detector measures the levels of volatile organic compounds (VOCs) when unfiltered, and methane gas when filtered. The equipment was used in the low range for this survey which reads from 0.5 to 2,000 parts per million (ppm).

The survey began on the front porch and then continued room-to-room from the first floor to the second floor (where applicable). Special attention was given to the base of toilets in the bathrooms, where methane is commonly detected in homes. No discernable odors were noted in any of the homes by our representative. Please refer to the attached field testing data sheets labeled *Indoor Air Monitoring* for details of the measurements recorded at each property.

The measurements indicate that the ambient background methane concentration was less than 5 ppm for the interior of each home, with the exception of the homes listed on the attached table, labeled *Indoor Air Monitoring Summary – Homes Greater than 5 ppm*. In this table, we have provided information pertaining to the apparent source of the methane (where discernible) and our suggestions for further investigation or repairs by a licensed plumber. We have also plotted the test results on a copy of a site plan provided by Lennar Homes, labeled *Methane Concentration Plot Plan*.

Please note that this report constitutes the first of two parts of this methane survey for the subject property. Appointments are still being scheduled to perform testing in the remainder of the homes in the Pebble Creek Village subdivision. PSI will present the findings for the remaining homes in a second report once the testing is completed.

Thank you for the opportunity to provide you with our services. Please contact our office if you have any questions.

Respectfully Submitted,
Professional Service Industries, Inc.



Robert V. Knowles
Vice-President



Keith A. Ingram, P.E.
Branch Manager

Attachment: *Summary of Indoor Air Testing by FID (8 of 8 pages)*
Indoor Air Monitoring field data sheets
Indoor Air Monitoring Summary – Homes Greater than 5 ppm
Methane Concentration Plot Plan

Summary of Indoor Air Testing by FID

[illegible]

Summary of Indoor Air Testing by FID

Test No.	Date Tested	Lot No.	Street Address	Background Methane Readings		
				<5 ppm	>5, <10 ppm	>10 ppm
16	10/05/06			X		
17	10/05/06			X		
18	10/05/06				X	
19	10/05/06			X		
20	10/05/06			X		
21	10/05/06			X		
22	10/05/06			X		
23	10/05/06			X		
24	10/05/06			X		
25*	10/05/06				X	
26	10/05/06			X		
27	10/05/06			X		
28	10/05/06			X		
29	10/05/06			X		
30	10/05/06			X		
31	10/05/06				X	
32	10/05/06			X		
33	10/05/06			X		
34	10/05/06			X		
35	10/05/06			X		
36	10/05/06			X		
37	10/05/06					X
**	10/5/06					X
**	10/5/06					X

Notes: * - SEE RETEST ON 10/11/06 for [REDACTED]
 ** - ONGOING INVESTIGATION RELATED TO SEWER PIPE BREAK.

Summary of Indoor Air Testing by FID

[illegible]

Summary of Indoor Air Testing by FID

Test No.	Date Tested	Lot No.	Street Address	Background Methane Readings		
				<5 ppm	>5 , <10 ppm	>10 ppm
49	10/2/06			X		
50				X		
51				X		
52					X	
53					X	
54				X		
55					X	
56				X		
57				X		
58				X		
59				X		
60						X
61				X		

Summary of Indoor Air Testing by FID

[illegible]

Summary of Indoor Air Testing by FID

[illegible]

Summary of Indoor Air Testing by FID

[illegible]

Summary of Indoor Air Testing by FID

[illegible]

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/04/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro E10

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
6:45	BACKGROUND		0.8		DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	0.6	—	FLOOR / SINK / DRAIN / PIPES
	DINING ROOM	1	0.4	—	
	KITCHEN	1	0.9	—	
	LAUNDRY				
	FAMILY ROOM	1	0.7		FIREFLACE (103)
	BATHROOM 1	1	0.9	✓	FLOOR / TOILET (NOT CAULKED) / SINK / PIPES
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.1	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.1	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/04/00

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FAD

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
6:16	BACKGROUND		0.1	—	DRIVEWAY
	FRONT PORCH	1	0.4	—	
	LIVING ROOM	1	0.7	—	FIREPLACE (1.3)
	DINING ROOM	1	0.7	—	
	KITCHEN		0.8	—	FLOOR/SINK/PIPES (1.1)
	LAUNDRY	2	1.4	—	
	FAMILY ROOM				
	BATHROOM 1	1	1.6	—	FLOOR/SINK/PIPES/TUB; WASH WASTER ON.
	BATHROOM 2	2	1.9	—	MASTER FLOOR/SINK/PIPES/SHOWER/TUB (2.4)
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	1.3	—	
	BEDROOM 2	2	1.4	—	NURSERY
	BEDROOM 3	2	1.4	—	
	BEDROOM 4				
	GARAGE	1	6.7	1.7	CONTROL JOINT NEAR MOTORCYCLE
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.8		
	OFFICE	1	0.7	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/04/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroT11

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
5:36	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM				
	DINING ROOM	1	0.0	—	
	KITCHEN	1	0.0	—	FLOOR/SINK/PIPES/DISH WASHING MOUNT (9.1)
	LAUNDRY	1	0.0	—	
	FAMILY ROOM	1	0.0	—	
	BATHROOM 1	1	0.0	—	FLOOR/TOILET/SINK
	BATHROOM 2	1	0.0	—	MASTER/FLOOR/TOILET (CAULKED)/SINK/TUB
	BATHROOM 3	2	0.0	—	FLOOR/SINK/PIPES/TOILET (CAULKED)/SHOWER
	BATHROOM 4				
	BEDROOM 1	1	0.0	—	
	BEDROOM 2	2	0.0	—	
	BEDROOM 3	2	0.0	—	
	BEDROOM 4	2	0.0	—	
	GARAGE	1	0.0	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	—	
	Front	2	0.0	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/04/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFTD

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
5:18pm	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM				
	DINING ROOM	1	0.0	—	
	KITCHEN	1	0.0	—	FLOOR/SINK/PIPE/Soap Bottle (10.2)
	LAUNDRY	1	0.0	—	
	FAMILY ROOM	1	0.0	—	
	BATHROOM 1	1	0.0	—	FLOOR/SINK/TOILET
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.0	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	—	
	OFFICE	1	0.0	—	
	Playroom	1	0.0	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/04/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFit

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
4:59	BACKGROUND	0.01	0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	0.0	—	
	DINING ROOM	1	0.0	—	
	KITCHEN	1	0.7	—	FLOOR / SINK / PIPES
	LAUNDRY	1	0.0	—	
	FAMILY ROOM	1	0.0	—	
	BATHROOM 1	1	0.5	—	FLOOR / SINK / TOILET (NOT CHAULED)
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.0	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/04/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MonoFlo

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
	BACKGROUND	1	1.2	—	F. BOUCH
	FRONT PORCH	1	1.2	—	
	LIVING ROOM				
	DINING ROOM	1	2.1	—	
	KITCHEN	1	1.6	—	FLOOR/SINK/PIPES
	LAUNDRY	1	2.0	—	
	FAMILY ROOM	1	1.6	—	
	BATHROOM 1	1	2.5	—	FLOOR/SINK/TOILET NOT CAULKED
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.7	—	
	HALL	2	1.2	—	
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.2	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/04/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroF10

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
4:30	BACKGROUND	1.6	1.6	—	F. Room #
	FRONT PORCH	1.6	1.6	—	
	LIVING ROOM	1	2.8	—	
	DINING ROOM	1	2.6	—	
	KITCHEN	1	2.8	—	FLOOR/SINK/TILES
	LAUNDRY				
	FAMILY ROOM	1	2.5	—	
	BATHROOM 1	1	2.2	—	FLOOR/SINK/TILES/TOILET (3.3 NOT CALLED)
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	2.5	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.8	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/04/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroF₂₁

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
4:13	BACKGROUND		3.1	—	DRIVEWAY (LANDSCAPING ACTIVITIES)
	FRONT PORCH	1	2.0	—	
	LIVING ROOM	1	2.5	—	
	DINING ROOM	1	2.6	—	
	KITCHEN	1	2.5	—	FLOOR/SINK/PIPES
	LAUNDRY				
	FAMILY ROOM	1	1.9	—	
	BATHROOM 1	1	1.7	—	FLOOR/SINK/TOILET/PIPES (2.1)
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.3	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.1	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/04/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MonoFit

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
3:55	BACKGROUND		2.8	—	STREET
	FRONT PORCH	1	1.8	—	
	LIVING ROOM	1	2.0	—	
	DINING ROOM	1	1.8	—	
	KITCHEN	1	1.9	—	FLOOR / SINK / PIPES
	LAUNDRY				
	FAMILY ROOM	1	1.3	—	
	BATHROOM 1	1	2.0	—	TUB / SINK / FLOOR / TOILET / PIPES
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	1.2	—	
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	1.6	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.8	—	
	EAT ROOM	1	1.3	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/04/2006

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroPID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
3:25pm	BACKGROUND		1.3	←	
	FRONT PORCH	1	1.5	—	
	LIVING ROOM	1	1.6	—	
	DINING ROOM	1			
	KITCHEN	1	1.5	—	FLOOR / SINK / DRAIN
	LAUNDRY				
	FAMILY ROOM	1	1.5	—	
	BATHROOM 1	1	1.6		FLOOR / TOILET / SINK / DRAIN (2.1)
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	6.8	3.0	CONTROL POINT BY FIDRE
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.2	←	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/04/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFET

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
3:10	BACKGROUND	1	0.4	—	
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	2	0.6	—	
	DINING ROOM	7			
	KITCHEN	1	0.5	—	SINK / PIPING / FLOOR
	LAUNDRY				
	FAMILY ROOM	1	0.9	—	
	BATHROOM 1	1	0.8	—	SINK / PIPING / TOILET
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.1	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/4

REPORT NO.: 465-80026

INSTRUMENT MODEL #:

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
			w/o	with filter	
2:35	BACKGROUND	1	0.0	0.0	
	FRONT PORCH	1	0.0	0.0	
	LIVING ROOM	3 1	0.7	—	
	DINING ROOM	2 1			
	KITCHEN	1	0.9	—	smk / pding / flr
	LAUNDRY				
	FAMILY ROOM	1	0.9	—	
	BATHROOM 1	1	1.7		smk / pding / toilet
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE ✓				
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0	—	
	GARAGE	1	3.0	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/4/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: _____

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
2:04	BACKGROUND	1	0.0		
	FRONT PORCH		0.0		
	LIVING ROOM		0.5		
	DINING ROOM	1	0.7	-	
	KITCHEN		1.0		
	LAUNDRY	2	0.8		35 on Tide Bottle Open / 25 close
	FAMILY ROOM		0.6		
	BATHROOM 1	1	1.6	-	shower / tub / toilet
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1		0.7		
	BEDROOM 2		0.2		"DOWNS ROOM"
	BEDROOM 3				
	BEDROOM 4				
	GARAGE				
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH				

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/4/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: _____

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
1:26	BACKGROUND	1	0.0	0 ✓	Perch
	FRONT PORCH	1	0	0	
	LIVING ROOM	1	22	21	
	DINING ROOM	1	22.5	27.6	
	KITCHEN	1	22.5	27.6	FLOOR STINK + psping - NO PROBLEM
	LAUNDRY	2	28.9		upstairs
	FAMILY ROOM		26		
	BATHROOM 1	1	28-350	28-	280 SMK / 100-350 @ toilet, not caulked
	BATHROOM 2	2	25.8		upstairs off HALL (toilet caulked)
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1		28.5		PURR ROOM
	BEDROOM 2		26.1		BOYS ROOM
	BEDROOM 3				
	BEDROOM 4				
	GARAGE				
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH		0	0	
	GARAGE		58	58.2	FLOOR

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE:

REPORT NO.: 465-60026

INSTRUMENT MODEL #:

MicroFID
w/heat

SN#:

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
12:39	BACKGROUND	0.0	0.0	0.0	Front Porch
	FRONT PORCH				
	LIVING ROOM		3.6	3.1	
	DINING ROOM	1	3.2	2.1	
	KITCHEN	1	3.0	3.0	Smoke / Draping
	LAUNDRY	1	3.4	3.0	
	FAMILY ROOM	1	3.7	3.5	
	BATHROOM 1	1	3.4	3.7	Down stairs - Toilet
	BATHROOM 2		3.0	2.8	Trk B
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE				
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH				
	Fireplace	1	3.0	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
6:35	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	0.2	—	
	DINING ROOM	1	0.0		
	KITCHEN	1	0.3	—	FLOOR/SINK/PIPES
	LAUNDRY	1	0.0	—	
	FAMILY ROOM				
	BATHROOM 1	1	0.5	—	SINK/PIPE/TOILET NOT CRAWLED 1.1
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.1	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro MITD

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
6:50 pm	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH				
	LIVING ROOM	1	0.3	—	
	DINING ROOM	1	0.4		
	KITCHEN	1	0.5	—	SMK / AIR / FLOOR
	LAUNDRY				
	FAMILY ROOM	1	0.1	—	
	BATHROOM 1	1	0.7	—	SMK / TOILET NOT CAULKED
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.0	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0		

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
5:50 pm	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH		0.0	—	
	LIVING ROOM				
	DINING ROOM	1	0.0	—	
	KITCHEN	1	0.0	—	
	LAUNDRY				
	FAMILY ROOM	1	0.2	—	
	BATHROOM 1	1	0.0	—	SINK / SHOWER / TOILET CAULKED
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	0.0	—	
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.0	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0		
	OFFICE	1	0.0		

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFit

SN#:

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
5:22pm	BACKGROUND		0.4	—	DRIVEWAY
	FRONT PORCH	1	0.1	—	
	LIVING ROOM	1	0.7	—	
	DINING ROOM	1	0.7	—	
	KITCHEN	1	1.3	—	FLOOR/SINK/PIPES 5.1 OPEN BOTTLE OF DETERGENT
	LAUNDRY	2	0.5	—	
	FAMILY ROOM	1	1.1	—	
	BATHROOM 1	1	1.2	—	SINK/PIPE/TOILET NOT CALLED
	BATHROOM 2	2	0.5	—	SHOWER/SINK/PIPES/TOILET CALLED
	BATHROOM 3	2	0.4	—	MASTER SINK/TUB/SHOWER/TOILET CALLED
	BATHROOM 4				
	BEDROOM 1	2	0.0	—	
	BEDROOM 2	2	0.0	—	
	BEDROOM 3	2	0.0	—	NURSERY
	BEDROOM 4	2	0.0	—	MASTER
	GARAGE	1	3.6	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Memo FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
5:07pm	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0		
	LIVING ROOM	1	6.4		
	DINING ROOM		6.4		
	KITCHEN	1	6.3		SINK 7.3 DISH WASHING LIQUID PRESENT
	LAUNDRY				
	FAMILY ROOM	1	6.6		FIREPLACE 7.7
	BATHROOM 1	1	6.7		TOILET IS MISSING. DRAIN COVERED w/ bag
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	4.9		
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0		

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFit

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
4:22 PM	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	0.9	—	
	DINING ROOM	1	0.9	—	
	KITCHEN	1	0.8	—	SINK / PIPES / FLOOR
	LAUNDRY	1	0.9	—	
	FAMILY ROOM	1	1.1	—	
	BATHROOM 1	1	1.8	—	SINK / TOILET CALLED
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	2.1	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.7	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FT

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
15:54	BACKGROUND		1.8	—	DRIVEWAY
15:55	FRONT PORCH	1	1.9	—	
	LIVING ROOM				
	DINING ROOM	1	2.9	—	
	KITCHEN	1	2.8	—	SINK / P.P.S. / FLOOR
	LAUNDRY	1	3.9		
	FAMILY ROOM	1	2.9	✓	
	BATHROOM 1	1	3.1	—	MASTER / SINK / SHOWER / TUB / SINK / TOILET CAULKED
	BATHROOM 2	1	2.7	—	SINK / TOILET
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	2.7	—	MASTER
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	1.7	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.7	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE:

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MonoFID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
15:08	BACKGROUND		2.2	—	DRIVEWAY
	FRONT PORCH	1	1.8	—	
	LIVING ROOM	1	3.1	—	
	DINING ROOM	1	3.4	—	
	KITCHEN	1	3.5	—	FLOOR / SINK / PIPING
	LAUNDRY	1	2.6	—	
	FAMILY ROOM				
	BATHROOM 1	1	3.1	—	FLOOR / SINK / TOILET CAULKED
	BATHROOM 2	1	4.7	—	SINK / PIPE / TUB / SHOWER / TOILET CAULKED 6.0 - MASTER
	BATHROOM 3	2	3.1	—	SINK / TUB / TOILET CAULK
	BATHROOM 4	2	1.5	—	
	BEDROOM 1	1	3.5	—	MASTER
	BEDROOM 2	2	1.8		
	BEDROOM 3	2	1.5		
	BEDROOM 4				
	GARAGE	1	4.6	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.4	—	
	PORCH	2	1.7	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: _____ SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
12:40	BACKGROUND		1.2	—	DRIVEWAY
	FRONT PORCH	1	1.1	—	
	LIVING ROOM				
	DINING ROOM	1	3.0	—	
	KITCHEN	1	3.4	—	FLOOR/SINK/PIPES
	LAUNDRY				
	FAMILY ROOM	1	4.0	—	FIREPLACE 9.7
	BATHROOM 1	1	4.5	—	SINK/PIPES/TOILET NOT CAULKED
	BATHROOM 2	2	4.1	—	SINK/PIPES/SHOWER/TOILET CAULKED
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	2	4.1	—	
	BEDROOM 2	2	3.9	—	MASTER/SINK/TUB/SHOWER/TOILET CAULKED
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	12.0	7.0	GAS CANS
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.6	—	
	OFFICE		3.6	—	
	PORCH	1	3.9	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS [REDACTED]

LOT #:

DATE: 10/05/00

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Model 417

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
14:27	BACKGROUND		1.3	—	DRIVEWAY
	FRONT PORCH	1	1.1	—	
	LIVING ROOM	1	2.5	—	
	DINING ROOM	1	2.6	—	
	KITCHEN	1	2.5	—	PIPES / SINK / FLOOR
	LAUNDRY				
	FAMILY ROOM	1	2.6		
	BATHROOM 1	1	3.1	✓	SINK / PIPES / TOILET NOT CAULKED
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	3.4	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.9		

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro Fit

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
13:45	BACKGROUND		2.0	—	DRIVEWAY
	FRONT PORCH	1	1.6	—	
	LIVING ROOM	1	6.1	6.2	FIRE PLACE 6.9
	DINING ROOM	1	6.6	6.4	
	KITCHEN	1	6.4	6.4	
	LAUNDRY	1	6.5	6.0	
	FAMILY ROOM				
	BATHROOM 1	1	60.0	84.1	AROUND TOILET CAULKED
	BATHROOM 2	1	6.8	6.5	AROUND TOILET BROWN CAULK 20.0w/DF. 6.0w/F
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	6.3	6.1	MASTER
	BEDROOM 2	2	5.5	—	NURSERY
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	1.1	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.2	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroT₁₀

SN#:

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
	BACKGROUND		2.0	—	DRIVEWAY
	FRONT PORCH	1	1.7	—	
	LIVING ROOM	1	3.0		
	DINING ROOM	1	2.8		
	KITCHEN	1	2.8		FLOOR / SINK / PIPES
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1	1	3.3	—	FLOOR / SINK / PIPES / SHOWER / TOILET CALKED
	BATHROOM 2	1	3.1		MASTER FLOOR / SINK / TUB / SHOWER / TOILET CALKED
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	3.2	—	
	BEDROOM 2	1	2.7	—	MASTER
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	2.4	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.8	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroTID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
12:53	BACKGROUND		4.3	—	DRIVE WAY
	FRONT PORCH	1	4.2	—	
	LIVING ROOM				
	DINING ROOM	1	3.6	—	
	KITCHEN	1	3.0	—	FLOOR / SINK / PIPES
	LAUNDRY	2	2.4	—	
	FAMILY ROOM	1	2.9	—	
	BATHROOM 1	1	3.9	—	SINK / PIPES / TOILET NOT CALLED
	BATHROOM 2	2	3.4	—	MASTER FLOOR / PIPES / SINK / TOILET CALLED / SHOWER
	BATHROOM 3	2	2.7	—	SINK / PIPES / SHOWER / TOILET CALLED
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	2.1	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.4	—	
	OFFICE	1	3.9	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:


DATE: 10/05/00

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFD

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
11:40	BACKGROUND		2.0		DRIVEWAY
	FRONT PORCH	1	1.3	—	
	LIVING ROOM				
	DINING ROOM	1	2.5	—	
	KITCHEN	1	2.7	—	FLOOR / SINK / PIPE
	LAUNDRY	1	2.2	—	
	FAMILY ROOM	1	2.7		
	BATHROOM 1	1	2.4	—	FLOOR / SINK / TOILET
	BATHROOM 2	1	2.7	—	FLOOR / SINK / SHOWER / TUB / TOILET CAULKED
	BATHROOM 3	2	2.2	—	FLOOR / SINK / SHOWER / TOILET CAULKED
	BATHROOM 4				
	BEDROOM 1	2	2.1		MASTER
	BEDROOM 2	2	2.1		NURSERY
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	1.2	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.8		
	YARD	1	0.6		@ BACKWALL BY LINING ROOM



TESTED FOR: LENNAR CORPORATION

RESIDENCE ADDRESS:

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID
w/o FILTER

SN#:

THESE TEST RESULTS APPLY ONLY TO THE SPECIFIC AREAS EVALUATED AND MAY NOT BE INDICATIVE OF THE ENTIRE HOME. REPORTS MAY NOT BE REPRODUCED, EXCEPT IN FULL, WITHOUT WRITTEN PERMISSION BY PROFESSIONAL SERVICE INDUSTRIES, INC.

TECHNICIAN: NDR

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

w/out FILTER

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
10:30	BACKGROUND		0.4		DRIVEWAY
	FRONT PORCH	1	10.7	0.4	
	LIVING ROOM	1	80.2	80.8	
	DINING ROOM	1	20.7 ⁺	79.2	READING w/out FILTER TAKEN w/ OPEN WINDOWS
	KITCHEN	1	19.0 ⁺	89.7	
	LAUNDRY				
	FAMILY ROOM	1	10.4 ⁺	68.0	
	BATHROOM 1	1	29.8 ⁺	70.5	
	BATHROOM 2	2	62.7	56.5	SHOWER / SINK / TOILET CAULKED
	BATHROOM 3	2	55.1	54.3	SHOWER / TUB / SINK / TOILET NOT CAULKED
	BATHROOM 4				
	BEDROOM 1	2	59.8	59.7	NURSERY
	BEDROOM 2	2	57.9	58.1	MASTER
	BEDROOM 3	2	55.9	56.1	
	BEDROOM 4				
	GARAGE	1	26.7 ⁺	28.1	
	HALL				
	CLOSET 1				* READINGS ON LEVEL 1 w/out FILTER WERE
	CLOSET 2				TAKING WITH DOORS & WINDOWS OPEN, AND
	CLOSET 3				CEILING FAN ON
	CLOSET 4				
	BACK PORCH				

TECHNICIAN: NDR

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
 WESTCOTT PLANTATION
 NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFit

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
10:03	BACKGROUND	0/0	0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	3.1	—	
	DINING ROOM	1	2.6	—	
	KITCHEN	1	2.6	—	SINK / PIPES / FLOOR
	LAUNDRY				
	FAMILY ROOM	1	4.9	—	FIREPLACE 49.7 NF / 7.1 W/F #
	BATHROOM 1	1	2.9	—	SINK / PIPES / TOILET NOT CAULKED
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	3.5	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	✓	

THESE TEST RESULTS APPLY ONLY TO THE SPECIFIC AREAS EVALUATED AND MAY NOT BE INDICATIVE OF THE ENTIRE HOME. REPORTS MAY NOT BE REPRODUCED, EXCEPT IN FULL, WITHOUT WRITTEN PERMISSION BY PROFESSIONAL SERVICE INDUSTRIES, INC.

TECHNICIAN: NDR

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/00

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micra 5D SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)	REMARKS
9:30	BACKGROUND		0.0	DRIVEWAY
	FRONT PORCH	1	0.0	
	LIVING ROOM	1	0.5	
	DINING ROOM	1	0.4	
	KITCHEN	1	0.5	FLOOR / SINK / PIPES
	LAUNDRY	2	1.2	
	FAMILY ROOM	1	0.5	
	BATHROOM 1	1	1.1	SINK / SHOWER / PIPES / TOILET
	BATHROOM 2	2	1.7	MASTER SINK / PIPES / SHOWER / TUB / TOILET CAULKED
	BATHROOM 3	2	1.4	SINK / PIPES / SHOWER / TOILET CAULKED
	BATHROOM 4			
	BEDROOM 1	1	1.0	
	BEDROOM 2	2	1.1	
	BEDROOM 3	2	1.2	
	BEDROOM 4	2	1.0	
	GARAGE	1	2.9	
	HALL			
	CLOSET 1			
	CLOSET 2			
	CLOSET 3			
	CLOSET 4			
	BACK PORCH	1	0.0	
	OFFICE	2	1.2	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: _____

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
9:20	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	0.0	—	
	DINING ROOM	1	0.0	—	
	KITCHEN	1	0.1	—	FLOOR / SINK / PIPES
	LAUNDRY	1	0.0	—	
	FAMILY ROOM				
	BATHROOM 1	1	0.0 ND	—	MASTER TOILET ^{CAVITY} / SINK / PIPES / SHOWER / TUB
	BATHROOM 2	1	0.5	—	TOILET NOT CALIBER / SINK
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	0.0	—	
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.1	←	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	←	

THESE TEST RESULTS APPLY ONLY TO THE SPECIFIC AREAS EVALUATED AND MAY NOT BE INDICATIVE OF THE ENTIRE HOME. REPORTS MAY NOT BE REPRODUCED, EXCEPT IN FULL, WITHOUT WRITTEN PERMISSION BY PROFESSIONAL SERVICE INDUSTRIES, INC.

TECHNICIAN: NDR

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
 WESTCOTT PLANTATION
 NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroT₃

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
8:45	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM				
	DINING ROOM	1	6.5	6.0	
	KITCHEN	1	6.5	6.5	FLOOR / SINK / PIPES
	LAUNDRY	1	7.1	6.2	
	FAMILY ROOM	1	6.5	6.8	
	BATHROOM 1	1	52.3	37.7	TOILET CAULKED (HIGH READING BY TOILET)
	BATHROOM 2	2	7.4	6.3	MASTER TOILET (CAULKED) / TUB / SHOWER / SINK / PIPES
	BATHROOM 3	2	8.0	5.9	TOILET / SHOWER / SINK
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.5	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	—	

THESE TEST RESULTS APPLY ONLY TO THE SPECIFIC AREAS EVALUATED AND MAY NOT BE INDICATIVE OF THE ENTIRE HOME. REPORTS MAY NOT BE REPRODUCED, EXCEPT IN FULL, WITHOUT WRITTEN PERMISSION BY PROFESSIONAL SERVICE INDUSTRIES, INC.

TECHNICIAN: NDQ

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE:

REPORT NO.: 465-60026

INSTRUMENT MODEL #:

MicroPip

SN#:

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
8:30	BACKGROUND		0.0	—	Driveway
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	0.1		
	DINING ROOM	1	0.0	—	
	KITCHEN	1	0.4		
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1	1	0.4		
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	2.0		
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0		

THESE TEST RESULTS APPLY ONLY TO THE SPECIFIC AREAS EVALUATED AND MAY NOT BE INDICATIVE OF THE ENTIRE HOME. REPORTS MAY NOT BE REPRODUCED, EXCEPT IN FULL, WITHOUT WRITTEN PERMISSION BY PROFESSIONAL SERVICE INDUSTRIES, INC.

TECHNICIAN: NDR

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/2006

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroTiger

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
8:15	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM				
	DINING ROOM	1	2.4	—	
	KITCHEN	1	2.6	—	FLOOR/SINK/FIRES
	LAUNDRY	1	2.1	—	
	FAMILY ROOM	1	2.3	—	FIRE PLACE 3.2
	BATHROOM 1	1	2.1	—	FLOOR/SINK/FIRES/TUB/TOILET (CALCULATED)
	BATHROOM 2	1	4.1		
	BATHROOM 3	1	4.2		TUB 9.7/SHOWER DRAIN 6.2/SINK DRAIN 4.7/TOILET 8.0
	BATHROOM 4				
	BEDROOM 1	1	1.8	—	
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	1.9	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	0	0.0		
	OFFICE	1	1.7	—	
	PORCH	2	1.4	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/00

REPORT NO.: 465-600 26

INSTRUMENT MODEL # Micro Fit

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
5:57pm	BACKGROUND		1.1	—	DOWNDRAW
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	0.2	—	
	DINING ROOM		0.0	—	
	KITCHEN	1	0.0	—	
	LAUNDRY				
	FAMILY ROOM	1	0.3	—	
	BATHROOM 1	1	0.9	—	SINK / TOILET / NOT CALLED
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	30.1	7.2		GAS CAN / WATER WATER 52.1 w/OUT FILTER 30.1 w/FILTER
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.3	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MICRO FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
5:00pm	BACKGROUND		1.4	—	DRIVEWAY
	FRONT PORCH	1	0.3	—	
	LIVING ROOM	1	1.3	—	
	DINING ROOM	1	1.2	—	
	KITCHEN	1	1.4	—	SINK / PIPES / FLOOR
	LAUNDRY				
	FAMILY ROOM	1	1.4	—	
	BATHROOM 1	1	1.9	—	SINK TOILET
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	1.6	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH				

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroTid

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
4:28 pm	BACKGROUND		0.9	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	19.6	18.1	FIREPLACE 23.5 w/o FILTER - 17.1 w/FILTER
	DINING ROOM	1	19.1	17.1	
	KITCHEN	1	19.4	17.9	FLOOR / SINK / POTS
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1	1	18.2	17.8	SINK / TUB / SHOWER / TOILET CAULKED w/FILTER 55.8 / 55.8
	BATHROOM 2	1	25.8	23.7	SINK / TUB / TOILET CAULKED 75.2 w/FILTER 73.7 w/FILTER
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	19.9	19.4	MASTER
	BEDROOM 2	1	16.9	16.7	
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.7	—	GARAGE DOOR OPEN
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.3	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #:

MicroTID

SN#:

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
4:06 pm	BACKGROUND		0.0	—	DOVEWIND
	FRONT PORCH	1	0.0		
	LIVING ROOM	1	0.0	—	FIREPLACE 0.7
	DINING ROOM	1	0.0		
	KITCHEN	1	0.4		FLOOR / SINK / SITES
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1	1	0.3	—	MASTER / SINK / SHOWER / TUB / TOWEL CARRIER 0.9
	BATHROOM 2	1	0.8	—	SINK / SHOWER / TOWEL CARRIER 1.2
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	0.2	—	MASTER
	BEDROOM 2	1	0.8	—	
	BEDROOM 3	1	0.7	—	
	BEDROOM 4				
	GARAGE	1	0.0	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0		

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: _____

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
3:17pm	BACKGROUND		0.8	—	DRIVEWAY
	FRONT PORCH	1	0.2	—	
	LIVING ROOM	1	0.7	—	
	DINING ROOM	1	0.6	—	
	KITCHEN	1	0.6	—	
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1	1	0.8	—	MASTER SINK / TUB / SHOWER / TOILET CAULKED
	BATHROOM 2	1	0.8	—	SINK / SHOWER / TOILET CAULKED
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	0.5	—	MASTER
	BEDROOM 2	1	0.8	—	
	BEDROOM 3	1	0.8	—	
	BEDROOM 4				
	GARAGE	1	0.1	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.4	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
	BACKGROUND		0.9		DRIVEWAY
	FRONT PORCH				
	LIVING ROOM	1	0.3		
	DINING ROOM	1	0.5		
	KITCHEN	1	1.1		
	LAUNDRY				
	FAMILY ROOM	1	1.3		
	BATHROOM 1	1	0.3		SINK / TOILET Hardware 0.8
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE				
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH				
	LOBBY	1	0.1		

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/05/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #:

MicroFID

SN#:

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
2:12pm	BACKGROUND		16.9		
	FRONT PORCH	1	2.5		
	LIVING ROOM	1	19.9	19.2	
	DINING ROOM	1	18.0	17.7	
	KITCHEN	1	18.7	16.9	FLOOR / SINK / PIPES
	LAUNDRY	1	18.6	18.9	
	FAMILY ROOM	1	18.3	17.9	FIRE PLACE 21.0
	BATHROOM 1	1	23.1	22.9	SINK / SHOWER / BATHROOM NOT CAULKED (WOOD) 270° / 280°
	BATHROOM 2	2	13.0	13.4	MASTER SHOWER / TUB / SINK / TOILET CAULKED
	BATHROOM 3	2	17.2	16.7	SINK / TUB / TOILET CAULKED
	BATHROOM 4				
	BEDROOM 1	2	14.2	13.9	MASTER
	BEDROOM 2	2	17.3	17.2	MURDER
	BEDROOM 3	2	15.9	15.6	
	BEDROOM 4	2	14.9	15.0	
	GARAGE	1	31.2	30.8	GAS CARLS
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	3.2		
	OFFICE	1	19.7	19.0	
	PORCH	2	17.1		

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
				<i>FILTER</i>	
12:59	BACKGROUND	—	2.0	—	DRIVEWAY
	FRONT PORCH	1	1.8	—	
	LIVING ROOM	1	5.5	4.5	
	DINING ROOM	1	5.3	4.6	
	KITCHEN	1	5.3	4.7	
	LAUNDRY				
	FAMILY ROOM	1	5.3	4.6	
	BATHROOM 1	1	4.7	4.3	SINK / TOILET NOT CAULKED (WOOD)
	BATHROOM 2	2	4.5	3.9	SINK / SHOWER / TOILET CAULKED
	BATHROOM 3	2	4.6	3.8	SINK / SHOWER / TUB / TOILET CAULKED
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	4.8		
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH				

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	FILTER		REMARKS
			READING (PPM)		
12:18	BACKGROUND		2.8	—	DRIVEWAY
	FRONT PORCH	1	2.1	—	
	LIVING ROOM	1	7.5	7.6	
	DINING ROOM		7.6	7.4	
	KITCHEN	1	7.4	7.3	
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1	1	6.9	6.8	MASTER TUB / SHOWER / SINK / TOILET CAULKED
	BATHROOM 2	1	2.0 9.0	8.7	TOILET NOT CAULKED (200+) w/FILTER (200+)
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	7.3	7.4	MASTER
	BEDROOM 2	1	8.6	7.9	
	BEDROOM 3	1	9.5	9.8	NURSERY
	BEDROOM 4				
	GARAGE	1	7.1	7.0	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	4.8	3.2	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
1200	BACKGROUND		2.3		Downe Way
	FRONT PORCH	1	2.1	—	
	LIVING ROOM	1	2.5	—	
	DINING ROOM	1	3.0	—	
	KITCHEN	1	2.9	—	SMOKE/FLOOR/PIPES
	LAUNDRY				
	FAMILY ROOM	1	2.7	—	
	BATHROOM 1	1	2.5	—	SMOKE/PIPES/TOILET NOT VENTED (WOOD) 3.5
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	3.9	—	By GAS TANK 5.7
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	2.1	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
11:36	BACKGROUND		0.6	—	DRIVEWAY
	FRONT PORCH	1	0.6	✓	
	LIVING ROOM				
	DINING ROOM	1	12.2	10.3	- AIR FRESHENERS USED IN HOUSE
	KITCHEN	1	12.3	10.1	FLOOR / SINK / PIPES 13.1
	LAUNDRY	1	4.6	9.8	
	FAMILY ROOM	1	12.7	10.1	
	BATHROOM 1	1	16.1	12.1	SINK / TOILET NOT CAULKED / WOOD FLOOR
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	9.5	9.2	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH		1.8	1.5	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
9:52	BACKGROUND				
	FRONT PORCH				
	LIVING ROOM	1	70.5	63.9	
	DINING ROOM	1	71.1	64.8	
	KITCHEN	1	87.9	64.0	
	LAUNDRY				
	FAMILY ROOM	1	69.5	64.3	
	BATHROOM 1	1	73.4	72.1	Bay DRAIN PIPE 900' w/ FILTER 500' w/o FILTER
	BATHROOM 2	2	52.5	55.5	SINK / TUB / SHOWER / TOILET NOT CALLED (61.7 w/o FILTER)
	BATHROOM 3	2	54.8	55.0	SINK / SHOWER / TOILET CALLED
	BATHROOM 4				
	BEDROOM 1	2	51.9	49.5	
	BEDROOM 2	2	52.2	51.1	MASTER
	BEDROOM 3	2	54.0	52.1	NURSERY
	BEDROOM 4				
	GARAGE	1	6.0	6.0	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH				
	CRACK IN Family Room		1450	2500 +	
	VENT PIPE IN Bathroom		2600	2600 +	
	CRACK IN KITCHEN		97.5	101.7	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #:

DATE: 10/06/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: _____

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
9:26	BACKGROUND		0.0		DRIVEWAY
	FRONT PORCH	1	0.0		
	LIVING ROOM	1	10.1	9.7	
	DINING ROOM	1	9.1	9.8	
	KITCHEN	1	10.1	10.0	
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1	1	45.5	34.6	By THE DRAIN PIPE 1000' WITH d/w/2 FILTER
	BATHROOM 2	2	7.9	8.4	MASTER SINK / TUB / SHOWER TOILET NOT CALLED
	BATHROOM 3	2	7.9	7.9	SINK / SHOWER / TOILET NOT CALLED
	BATHROOM 4				
	BEDROOM 1	2	7.9	8.8	MASTER
	BEDROOM 2	2	9.4	9.0	NURSERY
	BEDROOM 3	2	8.5	8.1	
	BEDROOM 4				
	GARAGE	1	2.0		
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH				
	OFFICE	2	5.5	6.5	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/09/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
4:54 pm	BACKGROUND		0.8	—	
	FRONT PORCH	1	0.1	—	
	LIVING ROOM	1	1.0	—	
	DINING ROOM	1	0.7	—	
	KITCHEN	1	0.4	—	FLOOR/SINK/PYES
	LAUNDRY				
	FAMILY ROOM	1	0.6	—	
	BATHROOM 1	1	0.4	—	SINK/SHOWER/TOWEL CARRIER (VINYL)
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	0.6	—	
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.2	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.4	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT # [REDACTED]

DATE: 10/09/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
4:26 pm	BACKGROUND		5.3		DRIVEWAY
	FRONT PORCH	1	4.8		
	LIVING ROOM	1	17.9	17.0	
	DINING ROOM	1	15.8	15.2	
	KITCHEN	1	16.6	15.1	FLOOR / SINK / PIPES
	LAUNDRY	1	15.1	14.7	
	FAMILY ROOM				
	BATHROOM 1	1	16.3	15.2	SINK / TOILET NOT CALLED (WOOD) *
	BATHROOM 2	2	14.8	14.8	MASTER / SINK / TUB / SHOWER / TOILET CALLED (W/M/L)
	BATHROOM 3	2	14.7	13.9	SINK / SHOWER / TOILET CALLED (W/M/L)
	BATHROOM 4				
	BEDROOM 1	2	15.5	15.6	MASTER
	BEDROOM 2	2	14.6	14.3	
	BEDROOM 3	2	14.7	14.1	
	BEDROOM 4		Ave = 15.0 - 4 = 11 Peak = None Noted		
	GARAGE	1	1.9		
	HALL				* HOMEOWNER HAD PAINTED CABINET DOORS
	CLOSET 1				IN GARAGE AREA
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	2.0		
	Flag	2	9.3	9.1	

FRESH AIR
CORRECTION = 4.0

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/09/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)	REMARKS
3:56 pm	BACKGROUND		4.9	Driveway
	FRONT PORCH	1	4.1	
	LIVING ROOM	1	3.1	
	DINING ROOM	1	3.2	
	KITCHEN	1	3.1	
	LAUNDRY			
	FAMILY ROOM	1	3.4	
	BATHROOM 1	1	3.2	
	BATHROOM 2			
	BATHROOM 3			
	BATHROOM 4			
	BEDROOM 1	1	3.0	
	BEDROOM 2			
	BEDROOM 3			
	BEDROOM 4			
	GARAGE	1	3.9	
	HALL			
	CLOSET 1			
	CLOSET 2			
	CLOSET 3			
	CLOSET 4			
	BACK PORCH			

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT # [REDACTED]

DATE: 10/09/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)	REMARKS
3:12 pm	BACKGROUND		4.3	DRIVEWAY
	FRONT PORCH	1	3.7	
	LIVING ROOM			
	DINING ROOM			
	KITCHEN	1	3.0	FLOOR/SINK/PANES
	LAUNDRY	1	2.3	
	FAMILY ROOM	1	3.1	
	BATHROOM 1	1	2.8	SINK/TOILET NOT CAULKED (WOOD) 3.6
	BATHROOM 2	1	2.0	MASTER SINK/SHOWER/TUB/TOILET CAULKED VINYL 3.7
	BATHROOM 3			
	BATHROOM 4			
	BEDROOM 1	1	2.8	MASTER
	BEDROOM 2			
	BEDROOM 3			
	BEDROOM 4			
	GARAGE	1	3.1	
	HALL			
	CLOSET 1			
	CLOSET 2			
	CLOSET 3			
	CLOSET 4			
	BACK PORCH	1	2.4	
	OFFICE	1	3.4	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/09/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFD

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
2:10 pm	BACKGROUND		2.8	—	DRIVEWAY
	FRONT PORCH	1	2.7	—	
	LIVING ROOM	1	2.4	—	
	DINING ROOM				
	KITCHEN	1	2.5	—	FLOOR / SINK / PIPES
	LAUNDRY	1	2.2	—	
	FAMILY ROOM				
	BATHROOM 1	1	2.6	—	SINK / TOILET NOT CAULKED (WOOD) 3.4
	BATHROOM 2	1	2.5	—	MASTER SINK / SHOWER / TUB / TOILET CAULKED (VINYL) 3.3
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	2.5	—	MASTER
	BEDROOM 2	2	2.6	—	
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	2.6	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	2.4	—	
	OFFICE	1	2.7	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/09/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro Fit

SN#: [REDACTED]

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
12:55	BACKGROUND		2.8	—	DRIVEWAY
	FRONT PORCH	1	2.5	—	
	LIVING ROOM				
	DINING ROOM	1	10.4	8.7	
	KITCHEN	1	10.1	8.8	FLOOR/SMOK / PIPES
	LAUNDRY				
	FAMILY ROOM	1	10.7	9.2	
	BATHROOM 1	1	9.9	9.6	SMOK / SHOWER / TOILET BATH CAULK VINYL 10.5/9.2
	BATHROOM 2	2	9.1	8.2	SMOK / SHOWER / TOILET CAULKED
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	10.3	9.6	
	BEDROOM 2	2	9.5	8.7	
	BEDROOM 3	2	9.5	8.9	
	BEDROOM 4	2	8.6	8.1	
	GARAGE	1	13.7	6.1	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.5	—	
	Pool Room	1	10.3	8.8	

Ave = $\frac{8.6 + 2.3}{2} = 6.3 \text{ ppm}$

FRESH AIR CORRECTION
= 2.3

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/09/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFD

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
9:55	BACKGROUND		1.0	—	DRIVEWAY
	FRONT PORCH	1	0.8	—	
	LIVING ROOM	1	6.7	6.8	
	DINING ROOM	1	6.9	7.0	
	KITCHEN	1	6.7	6.9	FLOOR/SINK GARBAGE DISPOSAL w/FILTER 13.7 *
	LAUNDRY				
	FAMILY ROOM	1	6.7	6.6	
	BATHROOM 1	1	5.3	5.2	SINK/TOILET (CAULKED) VINYL 7.0
	BATHROOM 2	2	8.0	7.8	MASTER SHOWER/TUB/SINK/TOILET CAULKED (VINYL) *
	BATHROOM 3	2	8.8	7.9	SINK/BATHS/SHOWER/TOILET CAULKED (VINYL)
	BATHROOM 4				
	BEDROOM 1	1	7.1	7.0	
	BEDROOM 2	2	8.0	7.9	
	BEDROOM 3	2	8.3	8.0	
	BEDROOM 4		Avg = 7.1 ppm - 1.4 = 5.7		
	GARAGE	1	3.4	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	2.5	2.4	Fresh Air Correction = 1.4

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/09/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
9:39	BACKGROUND		1.8	—	Driveway
	FRONT PORCH	1	1.4	—	
	LIVING ROOM	1	2.8	—	
	DINING ROOM	1	2.9	—	
	KITCHEN	1	3.0	—	SMOK / PIPES / FLOOR
	LAUNDRY				
	FAMILY ROOM	1	3.1	—	
	BATHROOM 1	1	2.8	—	SINK / TOILET NOT CALLED (WOOD)
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	4.2	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.7	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/09/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFD

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)	REMARKS
9:17	BACKGROUND		1.4	DRIVEWAY
	FRONT PORCH	1	0.9	
	LIVING ROOM	1	1.5	
	DINING ROOM	1	1.5	1
	KITCHEN	1	1.7	FLOOR/SINK/PIPES
	LAUNDRY			
	FAMILY ROOM	1	2.0	
	BATHROOM 1	1	2.3	SINK/TOILET NOT CAULKED (WOOD)
	BATHROOM 2			
	BATHROOM 3			
	BATHROOM 4			
	BEDROOM 1			
	BEDROOM 2			
	BEDROOM 3			
	BEDROOM 4			
	GARAGE	1	2.2	
	HALL			
	CLOSET 1			
	CLOSET 2			
	CLOSET 3			
	CLOSET 4			
	BACK PORCH			

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/09/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FD

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
8:30	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	0.0		
	DINING ROOM				
	KITCHEN	1	0.3	—	FLOOR/SINK/PIPES
	LAUNDRY				
	FAMILY ROOM	1	0.0	—	
	BATHROOM 1	1	0.4	—	SINK/PIPES / TOILET NOT CAULKED (WOOD) 1.5
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	1.9	←	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	—	
	OFFICE	1	0.0	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
 WESTCOTT PLANTATION
 NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/10/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
1:15pm	BACKGROUND		5.8	—	DRIVEWAY
	FRONT PORCH	1	4.9	—	
	LIVING ROOM	1	5.4	4.3	
	DINING ROOM	1	5.8	4.2	
	KITCHEN	1	5.7	4.5	FLOOR/SINK/PIPES
	LAUNDRY				
	FAMILY ROOM	1	5.4	4.6	
	BATHROOM 1	1	5.2	4.5	SINK/TOILET NOT CAULKED (WOOD)
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	4.2	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	3.8	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT # [REDACTED]

DATE: 10/10/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)	REMARKS
2:50	BACKGROUND	1	1.9	DRIVEWAY
	FRONT PORCH	1	1.5	
	LIVING ROOM	1	4.5	
	DINING ROOM	1	4.5	
	KITCHEN	1	4.5	FLOOR/SINK/PIES
	LAUNDRY	1	4.5	
	FAMILY ROOM			
	BATHROOM 1	1	4.0	SINK/SHOWER/TOILET NOT CAULKED (WOOD) 5.3
	BATHROOM 2	2	4.1	MASTER SINK/TUB/SHOWER/TOILET CAULKED (VINYL)
	BATHROOM 3	2	4.9	SINK/SHOWER/TOILET CAULKED (VINYL) 5.2
	BATHROOM 4			
	BEDROOM 1	1	3.9	
	BEDROOM 2	2	4.5	MASTER
	BEDROOM 3	2	4.3	NURSERY
	BEDROOM 4			
	GARAGE	1	2.2	
	HALL			
	CLOSET 1			
	CLOSET 2			
	CLOSET 3			
	CLOSET 4			
	BACK PORCH	1	2.4	
	OFFICE	1	4.1	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/10/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
7:00	BACKGROUND		0.0	—	
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	0.0	—	FIRE PLACE 2.0
	DINING ROOM	1	2.1	—	
	KITCHEN	1	1.2	—	SINK / STOVE / FLOOR
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1	1	1.0	—	MASTER SINK / SHOWER / TUB / TOILET CALLED (VINYL)
	BATHROOM 2	1	0.7	—	SINK / SHOWER / TOILET
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	0.9	—	MASTER
	BEDROOM 2	1	0.5	—	
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	2.8	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	—	
	OFFICE	1	0.5	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/10/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
1:39	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM				
	DINING ROOM	1	0.3	—	
	KITCHEN	1	0.5	—	FLOOR/SINK/PIPE
	LAUNDRY	2	1.3	—	
	FAMILY ROOM	1	0.4	—	
	BATHROOM 1	1	0.5	—	SINK/TOILET NOT CAULKED (WOOD)
	BATHROOM 2	2	1.1	—	MASTER/SINK/SHOWER/TUB/TOILET CAULKED (VINYL)
	BATHROOM 3	2	1.7	—	SINK/SHOWER/TUB/TOILET CAULKED (VINYL)
	BATHROOM 4				
	BEDROOM 1	2	1.1	—	MASTER
	BEDROOM 2	2	1.3	—	
	BEDROOM 3	2	1.9	—	
	BEDROOM 4	2	1.3	—	
	GARAGE	1	1.4	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.3	—	
	OFFICE	1	0.3	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/10/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FD

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
1:56	BACKGROUND		1.4	—	DRIVEWAY
	FRONT PORCH	4	1.3	—	
	LIVING ROOM	4	2.7	—	
	DINING ROOM	4	2.9	—	
	KITCHEN	1	3.2	—	FLOOR/SINK/PIPES
	LAUNDRY				
	FAMILY ROOM	1	3.5	—	
	BATHROOM 1	1	3.8	—	SINK/TOILET NOT CAULKED (WOOD) 15.1
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	4.0	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.8	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/10/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)	REMARKS
9:29	BACKGROUND		0.3	DRIVEWAY
	FRONT PORCH			
	LIVING ROOM	1	0.5	
	DINING ROOM			
	KITCHEN	1	0.4	SINK / PIPES / FLOOR
	LAUNDRY	1	3.1	
	FAMILY ROOM			
	BATHROOM 1	1	1.1	SINK / TOILET NOT CAULKED (WOOD)
	BATHROOM 2	1	1.9	MASTER / SINK / TUB / TOILET / TOILET CAULKED (VINYL)
	BATHROOM 3	2	2.7	SINK / SHOWER / TOILET CAULKED (VINYL)
	BATHROOM 4			
	BEDROOM 1	1	1.0	MASTER
	BEDROOM 2	2	1.8	
	BEDROOM 3	2	2.0	
	BEDROOM 4	2	2.0	
	GARAGE	1	3.4	
	HALL			
	CLOSET 1			
	CLOSET 2			
	CLOSET 3			
	CLOSET 4			
	BACK PORCH	1	0.3	
	OFFICE	2	2.0	
	YARD / ^{SIDE} LEFT OF HOUSE			

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/10/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
8:55	BACKGROUND		1.1		DRIVEWAY
	FRONT PORCH	1	0.9	—	
	LIVING ROOM	1	1.3	—	
	DINING ROOM	1	1.1		
	KITCHEN	1	1.3		FLOOR / SINK / APRES
	LAUNDRY				
	FAMILY ROOM	1	1.3		
	BATHROOM 1	1	1.3		SINK / TOILET NOT CAULKED (WOOD)
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE				
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.7		

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/10/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
8:38	BACKGROUND		0.8	—	DRIVEWAY
	FRONT PORCH	1	0.6	—	
	LIVING ROOM	1	1.0	—	
	DINING ROOM	1	0.8	—	
	KITCHEN	1	1.1	—	
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1	1	0.7	—	SINK / TOILET NOT CAULKED (WOOD)
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	3.0	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.0	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/10/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
8:28	BACKGROUND		0.1		D LVE
	FRONT PORCH	1	0.0		
	LIVING ROOM	1	3.0		
	DINING ROOM	1	2.9		
	KITCHEN	1	3.1		FLOOR / SINK / PILES
	LAUNDRY	1	2.3		
	FAMILY ROOM				
	BATHROOM 1	1	3.3		SINK / TOILET NOT CAULKED (WOOD)
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.8		
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.5		

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
 WESTCOTT PLANTATION
 NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/11/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)	REMARKS
3:05a	BACKGROUND		0.0	DRIVEWAY
	FRONT PORCH	1	0.0	
	LIVING ROOM	1	0.0	
	DINING ROOM	1	0.0	
	KITCHEN	1	0.0	
	LAUNDRY			
	FAMILY ROOM	1	0.0	
	BATHROOM 1	1	0.0	
	BATHROOM 2			
	BATHROOM 3			
	BATHROOM 4			
	BEDROOM 1			
	BEDROOM 2			
	BEDROOM 3			
	BEDROOM 4			
	GARAGE	1	0.2	
	HALL			
	CLOSET 1			
	CLOSET 2			
	CLOSET 3			
	CLOSET 4			
	BACK PORCH	1	0.0	

INDOOR AIR MONITORING

Re-test of 10/5 Test
AFTER Toilet inspected
by Plumber and
Recaulked.
PROJECT: PEBBLE CREEK on 10/9
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

TESTED FOR: LENNAR CORPORATION

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/11/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: _____

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
9:05	BACKGROUND		0.2		
	FRONT PORCH	1	0.0		
	LIVING ROOM	1	3.2		
	DINING ROOM	1	2.5		
	KITCHEN	1	2.5		FLOOR/SINK/PIPE
	LAUNDRY	1	7.2	3.1	
	FAMILY ROOM				
	BATHROOM 1	1	2.5		SINK/SHOWER/TUB/TOILET - MASTER
	BATHROOM 2	1	20.3		* SINK/TOILET CAULKED (WOOD) MODERATE ODOR 100.3 w/o FIL
	BATHROOM 3	2	3.5		SINK/SHOWER/TOILET CAULKED VINYL 100.1 w/FIL
	BATHROOM 4				
	BEDROOM 1	1	2.6		MASTER
	BEDROOM 2	2	3.3		NURSERY
	BEDROOM 3	2	3.5		
	BEDROOM 4	2	2.5		
	GARAGE	1	3.0		
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.3		
	OFFICE	2	1.7		

MISSING CAULK along
a section of toilet
(approx. 1" long)

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
 WESTCOTT PLANTATION
 NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/11/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
10:17	BACKGROUND		0.0	—	DRIVEWAY
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	2.7	—	
	DINING ROOM	1	2.9	—	
	KITCHEN	1	2.4	—	FLOOR / SINK / PIPES
	LAUNDRY				
	FAMILY ROOM	1	2.4	—	
	BATHROOM 1	1	6.3	5.8	SINK / TOILET NOT CAULKED (WOOD) w/o FL 20.1 w/F 19.7
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	3.3	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
 WESTCOTT PLANTATION
 NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/11/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
3:27	BACKGROUND		1.3	—	Driveway
	FRONT PORCH	1	0.8	—	
	LIVING ROOM	1	2.0	—	
	DINING ROOM	1	2.0	—	
	KITCHEN	1	2.4	—	Floor/Side/Ripr.
	LAUNDRY				
	FAMILY ROOM	1	2.1	—	
	BATHROOM 1	1	2.3	—	SHAL/TOLLET
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	3.7	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	1.2	—	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
 WESTCOTT PLANTATION
 NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/11/00

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFID SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
3:05	BACKGROUND		3.3		
	FRONT PORCH	1	2.3		
	LIVING ROOM	1	4.5		
	DINING ROOM	1	4.6		
	KITCHEN	1	4.0		FLOOR / SINK / PIPES
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1	1	3.4		MASTER SINK / SHOWER / TUB / TOILET CALLED
	BATHROOM 2	1	3.7		SINK / SHOWER / TOILET
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1	1	3.7		MASTER
	BEDROOM 2	1	3.5		
	BEDROOM 3	1	3.4		
	BEDROOM 4				
	GARAGE	1	3.8		
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.7		

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/11/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: _____

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
3:25	BACKGROUND		0.0	—	
	FRONT PORCH		0.0	—	
	LIVING ROOM				
	DINING ROOM				
	KITCHEN		7.8	7.0	TEST SITE
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1		110-130	105-130	TEST SITE
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE				
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH				

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/11/00

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
5:43	BACKGROUND		0.0		
	FRONT PORCH		0.0		
	LIVING ROOM				
	DINING ROOM				
	KITCHEN		180-200	165-180	
	LAUNDRY				
	FAMILY ROOM				
	BATHROOM 1	1	146.1	144.6	
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE				
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH				

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
 WESTCOTT PLANTATION
 NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/12/2006

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
10:10	BACKGROUND		0.0		
	FRONT PORCH	1	0.0		
	LIVING ROOM	1	91.2	90.4	
	DINING ROOM	1	87.1	86.9	
	KITCHEN	1	121.3	120.4	
	LAUNDRY				
	FAMILY ROOM	1	83.1	81.6	
	BATHROOM 1	1	93.3	91.8	TOILET MISSING. DRAIN PIPE RISER COVERED W/POURON'S
	BATHROOM 2	2	78.4	76.5	→ SPRING. BATHROOM DOOR MISSING.
	BATHROOM 3	2	80.7	78.7	→ MASTER
	BATHROOM 4				
	BEDROOM 1	2	78.2	76.9	MASTER
	BEDROOM 2	2	77.5	73.2	
	BEDROOM 3	2	69.1	68.9	NURSERY
	BEDROOM 4				
	GARAGE				
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH				
	Entry Hallway		90.6	89.7	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/12/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #:

Micro FID

SN#:

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
9:46	BACKGROUND		0.0		DRIVEWAY
	FRONT PORCH	1	0.1		
	LIVING ROOM				
	DINING ROOM	1	0.2	0.3	
	KITCHEN	1	0.3	0.2	
	LAUNDRY				
	FAMILY ROOM	1	0.2	0.1	
	BATHROOM 1	1	11.3	11.1	
	BATHROOM 2	2	4.0	3.7	MASTER
	BATHROOM 3	2	4.4	4.4	
	BATHROOM 4				
	BEDROOM 1	2	4.8	4.0	MASTER
	BEDROOM 2	2	4.2	4.1	
	BEDROOM 3	2	4.2	4.0	NURSERY
	BEDROOM 4				
	GARAGE				
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH				
	OFFICE	2	2.6	2.3	

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/13/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: MicroFID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
3:03pm	BACKGROUND				
	FRONT PORCH				
	LIVING ROOM	1	0.0		
	DINING ROOM	1	0.0		
	KITCHEN	1	0.0		
	LAUNDRY	1	0.0		
	FAMILY ROOM	1	0.0		
	BATHROOM 1	1	0.0		SINK/TOILET NOT CAULKED (WOOD)
	BATHROOM 2				
	BATHROOM 3				
	BATHROOM 4				
	BEDROOM 1				
	BEDROOM 2				
	BEDROOM 3				
	BEDROOM 4				
	GARAGE	1	0.0		
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0		

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
WESTCOTT PLANTATION
NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/13/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Micro FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)	REMARKS
5:12	BACKGROUND		0.0	
	FRONT PORCH	1	0.0	
	LIVING ROOM			
	DINING ROOM	1	0.3	
	KITCHEN	1	0.0	
	LAUNDRY			
	FAMILY ROOM	1	0.2	
	BATHROOM 1	1	0.6	SINK / TOILET NOT CAULKED (WOOD) 352 / 35.1
	BATHROOM 2	1	0.6	MASTER / SINK / SHOWER / TUB / TOILET CAULKED (VINYL)
	BATHROOM 3	2	0.3	SINK / SHOWER / TOILET CAULKED (VINYL)
	BATHROOM 4			
	BEDROOM 1	1	0.3	MASTER
	BEDROOM 2	2	0.0	
	BEDROOM 3	2	0.1	
	BEDROOM 4	2	0.0	
	GARAGE	1	0.5	
	HALL			
	CLOSET 1			
	CLOSET 2			
	CLOSET 3			
	CLOSET 4			
	BACK PORCH	1	0.0	
	Pool/Pan Conn	2	0.0	

THESE TEST RESULTS APPLY ONLY TO THE SPECIFIC AREAS EVALUATED AND MAY NOT BE INDICATIVE OF THE ENTIRE HOME. REPORTS MAY NOT BE REPRODUCED, EXCEPT IN FULL, WITHOUT

TECHNICIAN: WDR

INDOOR AIR MONITORING

TESTED FOR: LENNAR CORPORATION

PROJECT: PEBBLE CREEK
 WESTCOTT PLANTATION
 NORTH CHARLESTON, SC

RESIDENCE ADDRESS: [REDACTED]

LOT #: [REDACTED]

DATE: 10/16/06

REPORT NO.: 465-60026

INSTRUMENT MODEL #: Mexco FID

SN#: _____

TIME	LOCATION	LEVEL	READING (PPM)		REMARKS
1:03	BACKGROUND		0.0	—	
	FRONT PORCH	1	0.0	—	
	LIVING ROOM	1	0.0	—	
	DINING ROOM	1	0.0	—	
	KITCHEN	1	0.0		FLOOR / SINK / PIPES
	LAUNDRY				
	FAMILY ROOM	1	0.0	—	
	BATHROOM 1	1	0.0		SHOWER / SINK / TOILET CAULKED (VINYL)
	BATHROOM 2	2	0.0	—	MASTER (SHOWER / SINK / TUB / TOILET CAULKED (VINYL)
	BATHROOM 3	2	0.1	—	SINK / SHOWER / TOILET CAULKED (VINYL)
	BATHROOM 4				
	BEDROOM 1	2	0.0	—	
	BEDROOM 2	1	0.0	—	
	BEDROOM 3	2	0.0	—	MASTER
	BEDROOM 4	2	0.0	—	
	GARAGE	1	0.0	—	
	HALL				
	CLOSET 1				
	CLOSET 2				
	CLOSET 3				
	CLOSET 4				
	BACK PORCH	1	0.0	—	
	OFFICE	2	0.0	—	

THESE TEST RESULTS APPLY ONLY TO THE SPECIFIC AREAS EVALUATED AND MAY NOT BE INDICATIVE OF THE ENTIRE HOME. REPORTS MAY NOT BE REPRODUCED, EXCEPT IN FULL, WITHOUT

TECHNICIAN: ADR

Indoor Air Monitoring Summary – Homes Greater than 5 ppm

Lot #	Street Address	Backgrnd. Reading Average (ppm)	Apparent Source	Remarks & Recommendations	Date Tested
		5.1	1st Floor Toilet.	Peak 200+ @ Toilet. Reseat and seal toilet, adjust drainpipe height if needed. Recaulk.	10/6/06
		21 to 58	1st Floor Toilet. Uncaulked toilet on wood floor	Peak @ Toilet = 350 ppm, Reseat and seal toilet, adjust drain pipe height if needed.	10/4/06
		18.7	1st Floor Toilet with caulk	Peak 55 to 75 @ Toilet. Reseat and seal toilet, adjust drainpipe height if needed. Recaulk.	10/6/06
		14.8	1st Floor Uncaulked toilet on wood floor	Peak @ Toilet = 270 ppm. Reseat and seal toilet, adjust drainpipe height if needed.	10/05/06
		6.3	1st Floor Uncaulked Toilet on Wood Floor	Peak 130 @ Toilet. Reseat and seal toilet, adjust drainpipe height if needed.	10/6/06
		10.3	No source located	Check Seal @ Toilet. Repair as needed.	10/6/06
		67.3	Broken and repaired sewer pipe, missing 1st Floor toilet, methane trapped below slab venting through slab openings	Seal floor at openings and exposed cracks in concrete, replace toilet in 1 st floor Bathroom. Vent sub slab soils.	10/5/06
		9.5	Broken and repaired sewer pipe, missing 1st Floor toilet, methane trapped below slab venting through slab openings	Seal floor at openings and exposed cracks in concrete, replace toilet in 1 st floor Bathroom. Vent sub slab soils.	10/5/06
		6.5	1 st floor Toilet missing. Removed by Homeowner (?)	Peak 40 at bathroom. Install toilet.	10/5/06
		4.5	1st Floor Toilet.	Peak 84 @ Toilet. Reseat and seal toilet, adjust drainpipe height if needed. Recaulk.	10/05-10/11/06
		6.3	1st Floor Toilet.	Peak Rdg of 38 in Bathroom only. Reseat and seal toilet, adjust drainpipe height if needed. Recaulk.	10/5/06
		11	None located	Suspect 1 st floor Toilet on wood floor. Check Seal @ Toilet. Repair as needed.	10/9/06
		6.3	1st Floor Toilet. Damaged Caulk on Toilet	Peak @ 8.2 at Toilet on vinyl. Caulk damaged. Reseat and seal toilet, adjust drainpipe height if needed. Recaulk.	10/9/06
		< 5	Uncaulked 1st Floor Toilet. on Wood Floor	Peak 34 @ 1 st floor Toilet. Reseat and seal toilet, adjust drainpipe height if needed.	10/9/06
		5.7	Garbage Disposal and possibly 1st Floor Toilet.	Peak at disposal of 12. Check Sink Trap for leaks. Reseat and seal toilet, adjust drainpipe height if needed. Recaulk	10/9/06
		<5	Uncaulked 1st Floor Toilet. on Wood Floor	Peak 35 @ 1 st floor Toilet. Reseat and seal toilet, adjust drainpipe height if needed.	10/13/06

PLAN INTENTIONALLY REMOVED FOR PRIVACY