





# LANDFILL CONSTRUCTION AND OPERATIONS WORKSHOP

# LANDFILL CONSTRUCTION AND OPERATIONS WORKSHOP

No.	Module	Presenter
1	Importance of Proper Landfill Management	P. Ruesch
2	Landfill Construction Part I	M. Elizondo
3	Landfill Construction Part II	J. Davila
4	Landfill Operations Part I	M. Elizondo
5	Landfill Operations Part II	M. Elizondo
6	LFG Basics and GCCS	J. Davila
7	LFG Utilization Technologies	J. Davila
8	Open Dump Closure	P. Ruesch









# Module No. 2 Landfill Construction Part I Marcos Elizondo, WCA





### Purpose

- Technical guide explains minimum controls and testing needed during landfill construction
- Including:
  - Liner system
  - Leachate collection system
  - Groundwater monitoring wells
  - LFG monitoring probes

# Landfill



## Siting

- Location/siting restrictions
- Physical & social aspects
- Environmental impact assessment

# Siting

- Physical conditions
  - Geology
  - Hydrogeology
  - Groundwater
  - Climate
  - Surface water (rivers, lakes, creeks)
  - Geological faults
  - Active seismic zones
  - Unstable zones
  - Endangered species


# Siting

- Social Considerations
  - Schools or childcare facilities
  - Churches
  - Hospitals
  - Cemeteries
  - Commercial or residential developments
  - Recreational areas
  - Historic sites
  - Archeological sites
  - Sites with exceptional aesthetic quality
- Public, local government, and community involvement


## Cell Components

- Liner system
  - 60 cm compacted soil
  - $k = 1X10^{-7} \text{ cm/s}$
  - 60-mil (0.152 cm) HDPE geomembrane
  - Smooth or textured on flat surfaces
  - Textured (both sides) on slopes
- Leachate collection system

#### **Liner Components**



#### **Liner Components**



- Any liquid that goes through the waste turns into leachate
- Leachate tends to move downward to the bottom of the landfill
- Leachate is collected by the liner system
- The collection system transports leachate to the sumps
- The system is design to control the leachate levels on the liner system

- Main components
  - Drainage layer
  - Collection pipe
  - Sumps
  - Risers and pump system
  - Leachate management

- Drainage layer
  - Granular
    - Sand
    - Gravel
  - Geosynthetic
    - Geonet
    - Geotextile



- Collection pipe
  - PVC

High Density Polyethylene (HDPE)



Sump



Riser and pump system





Leachate management

- Ponds
- Tanks
- On-site treatment
- Off-site treatment




### Construction Quality Control/ Assurance

- Quality Control/Assurance (QC/QA) includes: monitoring, testing, and recommendations during construction.
- Personnel must be familiarized with procedures, specifications and construction plans.
- Monitoring and documentation during all phases of the construction.
- Recommended for all landfill construction phases.




- LFG is generated by the anaerobic decomposition of organic waste.
- Composition is ~ 50% methane, 50% carbon dioxide, traces of other compounds.



- Safety
  - Odors
  - Explosions
  - Greenhouse gases







- Perimeter monitoring system
  - Monitoring probes
  - Typically monitored quarterly
  - Danger at 5% methane by volume



- Control systems
  - Passive
    - Vent wells
    - Individual flares
  - Active
    - Flares



- 60 cm soil layer
- Permeability < 1 x 10<sup>-7</sup> cm/s
- Liquid Limit > 30
- Plasticity Index > 15
- % of material passing 0.075 mm sieve > 30%
- Maximum rock size = 25 cm
- Rock or stone content < 10%</li>



- In-situ soils can be used if specifications are met
  - 1 test every 5,000 m<sup>2</sup>
  - Thickness check 1 every 500 m<sup>2</sup>

- Stormwater system constructed to remove water around bottom liner system
- Minimize flow of water towards/on bottom liner
- Stormwater must be removed from bottom liner system as soon as possible
- If water can't drain by gravity, use pumps

- Liner hydration
  - Very important
  - Required for compaction
  - Add water during mixing
  - Water must be clean (no leachate)



- Lumps & rock size
  - Lumps must be reduced to obtain target permeability
  - No rocks or stones> than 25 mm



Soil compaction



- Protective soil layer
  - 60 cm minimum between geomembrane and waste
  - 30 cm minimum between leachate collection system and waste
  - Must permit leachate to flow to drainage layer
  - Permeability must be > 1 x 10<sup>-4</sup> cm/s, or provide ways to remove leachate through other soils or piping

Protective soil layer



- Quality assurance testing
- Field Density
  - Nuclear gauge (~ \$8,000)
  - Manual test equipment (~ \$200)



#### Geomembrane Liner

 Geomembrane – High Density Polyethylene flexible liner

- Thickness 60 mils (0.152 cm)
- Liner installed over soil



- Fabricated with raw materials
- Delivered in rolls
- Inspected for signs of damages or defects when received
- Protect from soft humid, rocky or uneven grounds
- Do not store stacked more than 5 rolls high



Base preparation



- Geomembrane installation
  - Avoid damage to base and geomembrane






- Geomembrane installation
  - Do not install during inclement weather
    - Rain
    - High winds
  - During high winds, stop construction and secure geomembrane to base using tires, extra rolls of material, sand bags or other heavy material that will not damage the geomembrane



- Equipment
  - Use only low-ground pressure (LGP) equipment such as:
    - Golf carts
    - Small four-wheelers
    - Other equipment with rubber tires floor pressure < 35 kPa and a total weight = 340 kg (including load)



Fusion welding



Extrusion welding



Pressure test for fusion welding



Suction test for extrusion welding



Destructive Testing at unions



- Repairs and tests
  - Continuous visual inspections to detect holes, punctures, perforations, tears or breaks
  - Repairs must be done using welded patches
  - All repairs and unions must be tested






- Anchor trench and fill material
  - Anchor trench must be located around all edges of the geomembrane which will not be used for future connections to next cell



- Anchor trench and fill material
  - Anchor trench must be filled with compacted soil



- Protective soil and drainage layer materials
  - Protective soil and drainage layer of 60 cm
  - Install during the cooler hours of the day
  - Install in fingers to control and minimize wrinkles
  - Install upwards on slopes
  - Install with light equipment such as a low ground pressure bulldozer
  - Continuous supervision during construction by a CQA professional is recommended

Protective layer and granular drainage



Protective soil layer installed in fingers



#### Thank You

Module No. 2

Landfill Construction Part I

Marcos Elizondo, Vice-president of Operations and Engineering
WCA Waste Corporation

melizondo@wcamerica.com +1 (281) 808-5262

# LANDFILL CONSTRUCTION AND OPERATIONS WORKSHOP







